INSPECTION REPORT



For the Property at:

3700 S. CENTRAL

CICERO, IL 60804

Prepared for: JANE DOE

Inspection Date: Thursday, October 17, 2013

Prepared by: Thomas Jansson





Acuity Home Inspection Service 1936 W Estes Ave Chicago, IL 60626 312-217-5249 IL Lic. 450.003340 exp 11/30/14 www.insightinspec.com tj@insightinspec.com



January 5, 2014

Dear Jane Doe,

RE: Report No. 1398, v.2 3700 S. Central Cicero, IL 60804

Thank you for choosing Acuity. If you have questions about your inspection or report, please let me know. You can always e-mail me at tj@insightinspec.com. The fastest way to reach me is usually my cell: 312.217.5249.

This is an interactive report. Many of the items have blue hyperlinks which connect you to a home inspection database. To navigate quickly between sections, use the tabs at the top of the page.

Where action is recommended, only licensed and insured specialty contractors should be used. When researching costs, you are encouraged to obtain three signed estimates from three different, licensed and insured contractors. Always be sure to compare "apples to apples." Price disparities may indicate different levels of workmanship, design, or materials.

Contractors may uncover additional issues that were not detected or discussed at the inspection. This isn't unusual. Home inspections are non-invasive, non-destructive, limited, visual inspections, performed by a generalist. A specialist will have more detailed knowledge in his or her particular field, and may be authorized to perform certain tasks that a home inspector, performing a normal home inspection, would never do (like removing a wall, spending an hour under a sink, or disassembling the furnace.)

The inspection is a "snapshot in time." It's a look at the house as it appeared on inspection day. Ongoing maintenance, and ongoing monitoring, are important parts of home ownership. There's no such thing as a "maintenance-free" house.

Sincerely,

Thomas Jansson on behalf of Acuity Home Inspection Service

APPENDIX

INTERIOR

3700 S. Central, Cicero, IL October 17, 2013

EXTERIOR

ROOFING

www.insightinspec.com

PLUMBING

COOLING

HEATING

Note: For the purpose of this report the building is considered to be facing West.

STRUCTURE

This Summary outlines potentially significant issues from a cost or safety standpoint. This section is provided as a courtesy and cannot be considered a substitute for reading the entire report. Please read the complete document.

Roofing

SUMMARY

SLOPED ROOFING \ Asphalt shingles

Condition: • Missing, loose or torn

Shingles are showing signs of advanced age and wear. Damage and deterioration noted throughout roof.

Roofing replacement is recommended at this time.

Multiple layers were observed. Tear-off required when replacing.

Exposed sheathing at south; chance of water entry, chance of rot. Some plank sheathing replacement may be necessary when replacing roof.

Obtain roof replacement estimates from qualified roofers prior to closing.

Implication(s): Chance of water damage to contents, finishes and/or structure

Exterior

ROOF DRAINAGE \ Downspouts

Condition: • Too few

Implication(s): Chance of water damage to contents, finishes and/or structure

Task: Improve Time: Immediate

WALLS \ Brick, stone and concrete

Condition: • Masonry deterioration

Masonry deterioration; brick erosion/spalling noted at south, southwest, and north. Typical defect for buildings of this age and type. Mortar repair and brick maintenance is needed throughout. Consult with licensed masonry contractor for whole-house tuck-pointing quote prior to closing.

Implication(s): Weakened structure | Chance of structural movement

Condition: • Mortar deterioration

Mortar cracks noted throughout. Structural movement suspected. Have mortar repaired by licensed masonry contractor as needed throughout prior to closing.

Implication(s): Chance of water entering house | Weakened structure | Chance of structural movement

Location: Throughout

Task: Repair Time: Immediate

www.insightinspec.com

3700 S. Central, Cicero, IL October 17, 2013

SUMMARY F

ROOFING

EXTERIOR

STRUCTURE ELEC

HEATING

COOLING

PLUMBING

INTERIOR

APPENDIX

PORCHES, DECKS, STEPS, PATIOS AND BALCONIES \ Steps and landings

Condition: • Masonry or concrete cracking

Previous cosmetic repairs. Front steps are cracking. Loose concrete, loose handrail. Have steps replaced by licensed

masonry contractor prior to closing. **Implication(s)**: Weakened structure

Location: Front Task: Replace Time: Immediate

Structure

General

- Possible insect activity noted at NE corner of building at basement. Unidentified "sawdust-like" material was observed in electrical panel. This material may be related to insect activity. Further evaluation by a licensed pest contractor specializing in wood-destroying organisms is recommended prior to closing.
- Main stairway is pulling away from trim stringer at north. It appears that the top of the stairway has moved approximately 1-1/2" laterally away from the wall. Further review and repair as needed by licensed structural contractor is recommended prior to closing.

FOUNDATIONS \ Performance opinion

Condition: • Suspect

Fully finished basement prevented direct observation of the foundation. Foundation performance is suspect due to exterior masonry cracks and elevated moisture levels detected in basement. See water intrusion notes in "Interior" section of this report.

Further evaluation of foundation by waterproofing specialist is recommended prior to closing. Further evaluation of foundation (when exposed) by licensed home inspector or structural engineer is recommended.

Implication(s): Chance of structural movement

Task: Further Evaluation

WALLS \ Solid masonry walls

Condition: • Lintels rusting

Have lintels serviced as needed when tuck-pointing exterior of structure. It appears that a window was removed and bricked up at the north. The lintel was left in the wall, and is now deteriorating and pushing the bricks apart. Have repaired as needed by licensed masonry contractor.

Implication(s): Weakened structure | Chance of structural movement

Location: Throughout

Task: Service
Time: Immediate

3700 S. Central, Cicero, IL October 17, 2013 www.insightinspec.com

SUMMARY ROOFING EXTERIOR STRU

R STRUCTURE

ELECTRICA

HEATING

COOLING

PLUMBING

INTERIOR

APPENDIX

Electrical

SERVICE BOX, GROUNDING AND PANEL \ Distribution fuses/breakers

Condition: • <u>Double taps</u> **Implication(s)**: Fire hazard

Location: Panel Task: Correct Time: Immediate

DISTRIBUTION SYSTEM \ Outlets (receptacles)

Condition: • Reversed polarity Implication(s): Electric shock

Location: Addition Task: Correct Time: Immediate

Condition: • Arc Fault Interrupter (AFI) needed

Current national standards require Arc Fault Interrupter (AFI) outlets for all bedroom outlet circuits. Have AFI breakers added as needed by licensed electrician to enhance the safety of the electrical system. For more information about AFI protection, see "Appendix" section of this report.

Location: Panel Task: Install Time: Immediate

Heating

GAS FURNACE \ Ducts, registers and grilles

Condition: • Poor location

Opening in return plenum can lead to carbon monoxide entering the living space. Carbon monoxide is a colorless, odorless, deadly poisonous gas. This opening must be properly sealed to prevent carbon monoxide poisoning. Have furnace reviewed and corrected as needed by licensed HVAC tech prior to use.

Location: Furnace Task: Correct Time: Immediate

Plumbing

WATER HEATER - GAS BURNER AND VENTING \ Venting system

Condition: • Improper material

Flexible ductwork used as vent connector. Improper slope; may cause backdrafting of combustion gasses into house. Have reviewed by licensed plumbing or heating contractor and repair as needed.

Implication(s): Equipment not operating properly | Hazardous combustion products entering home

www.insightinspec.com

3700 S. Central, Cicero, IL October 17, 2013 SUMMARY

ROOFING

EXTERIOR

STRUCTURE

HEATING

COOLING

PLUMBING

INTERIOR

APPENDIX

Interior

WALLS \ Plaster or drywall

Condition: • Water damage

Very high moisture levels noted at basement interior at south and east. Advanced rot and deterioration observed at weight room (south side near front of building). Mold or mildew staining observed at south and east.

Extremely high moisture levels were observed; it is almost a certainty that rot and mold will be found once the drywall has been removed.

Mold testing was not performed at this inspection.

Drywall should be removed as needed throughout basement, to facilitate further investigation and repair. Foundation cracks are probably present, but could not be directly observed due to the presence of drywall. Have basement leaks repaired by licensed basement waterproofing contractor prior to closing.

Implication(s): Cosmetic defects Location: Throughout Basement Task: Further evaluation/Repair

Time: Immediate

Condition: • Cracked

Large wall crack noted at south, second floor. Indication of structural movement. Have repaired as needed prior to closing.

Task: Repair

Time: Ongoing

CEILINGS \ General

Condition: • Water damage

Water damage, blistering plaster noted at second floor, east. Area was scanned with moisture meter; elevated moisture levels were detected. An active leak is suspected. May be related to either failed chimney flashing or the overall poor condition of the roof. Have water source positively identified and repaired prior to repair of interior finished surfaces.

Elevated moisture levels may support mold growth. Mold testing was not performed at this inspection.

Implication(s): Cosmetic defects | Chance of movement

This is the end of the summary section. The remainder of the report deals with individual systems in more detail, and may list conditions that were not included in the summary section. Please read the entire report.

www.insightinspec.com 3700 S. Central, Cicero, IL October 17, 2013

SUMMARY

ROOFING

STRUCTURE ELECTRICAL

COOLING

PLUMBING

APPENDIX

Description

General: • The Description section identifies components in the home by material or type. This is provided as an inventory, and no observations or comments on conditions are included here.

Sloped roofing material: • Asphalt shingles

Probability of leakage: • High

Limitations

Inspection performed: • With binoculars from the ground • From roof edge

Recommendations

General

• Roofs may leak at any time. Leaks often appear at roof penetrations, flashings, changes in direction or changes in material. A roof leak should be addressed promptly to avoid damage to the structure, interior finishes and furnishings. A roof leak does not necessarily mean the roof has to be replaced. We recommend an annual inspection and tune-up to minimize the risk of leakage and to maximize the life of roofs.

SLOPED ROOFING \ Asphalt shingles

Condition: • Missing, loose or torn

Shingles are showing signs of advanced age and wear. Damage and deterioration noted throughout roof.

Roofing replacement is recommended at this time.

Multiple layers were observed. Tear-off required when replacing.

Exposed sheathing at south; chance of water entry, chance of rot. Some plank sheathing replacement may be necessary when replacing roof.

Obtain roof replacement estimates from qualified roofers prior to closing.

Implication(s): Chance of water damage to contents, finishes and/or structure



Missing shingles

3700 S. Central, Cicero, IL October 17, 2013

SUMMARY

ROOFING

EXTERIOR

STRUCTURE ELECTRICAL

HEATING

COOLING

PLUMBING

APPENDIX



Exposed sheathing



Missing, loose or torn



Roof is in poor condition

3700 S. Central, Cicero, IL October 17, 2013

SUMMARY

ROOFING

EXTERIOR

STRUCTURE

ELECTRIC

HEATING

COOLIN

PLUMBIN

INTERIOR

APPENDIX




Exposed sheating

SLOPED ROOF FLASHINGS \ Chimney flashings

Condition: • Not let into mortar joints

Chimney is "flashed" with tar. Although common, tar "flashing" is a problematic solution to roof leaks. This is a low-cost alternative to real chimney flashing. May leak unexpectedly; regular maintenance is needed to prevent roof leaks. You are encouraged to have the chimney properly flashed with metal flashing when replacing roof. Consult with licensed roofing contractor for repair estimates.

Implication(s): Chance of water damage to contents, finishes and/or structure



3700 S. Central, Cicero, IL October 17, 2013 www.insightinspec.com

SUMMARY ROOFING EXTERIOR STRUCTURE ELECTRICAL HEATING COOLING PLUMBING INTERIOR APPENDIX



Chimney "flashed" with roofing cement

www.insightinspec.com

3700 S. Central, Cicero, IL October 17, 2013

SUMMARY

ROOFING

EXTERIOR

STRUCTURE ELECTRICAL

PLUMBING

APPENDIX

Description

Gutter & downspout material: • Aluminum

Gutter & downspout type: • Eave mounted

Downspout discharge: • Below grade

Lot slope: • Flat

Wall surfaces - masonry: • Brick

Driveway: • Concrete Walkway: • Concrete

Exterior steps: • Concrete

Fence: • Wood

Limitations

Inspection limited/prevented by: • Car/storage in garage

Exterior inspected from: • Ground level

Recommendations

ROOF DRAINAGE \ Gutters

Condition: • Basement leakage is often caused by conditions on the exterior of the home. Basements aren't built like boats, and if water is allowed to collect outside of foundation walls, it will leak through into the basement. It's important that gutters and downspouts collect roof water and carry it away from the house. Similarly, lot grading around the house should slope down away from the building so that surface water from rain and melting snow is directed away from the building, rather than toward the foundation.

ROOF DRAINAGE \ Downspouts

Condition: • Too few

Implication(s): Chance of water damage to contents, finishes and/or structure

Task: Improve Time: Immediate


3700 S. Central, Cicero, IL October 17, 2013

SUMMARY

ROOFING

EXTERIOR

PLUMBING



WALLS \ Brick, stone and concrete

Condition: • Masonry deterioration

Masonry deterioration; brick erosion/spalling noted at south, southwest, and north. Typical defect for buildings of this age and type. Mortar repair and brick maintenance is needed throughout. Consult with licensed masonry contractor for whole-house tuck-pointing quote prior to closing.

Implication(s): Weakened structure | Chance of structural movement



Masonry deterioration



Masonry deterioration

3700 S. Central, Cicero, IL October 17, 2013

SUMMARY

ROOFING

EXTERIOR

STRUCTUR

ELECTRIC

HEATING

COOL

PLUMBIN

INTERIOR

APPENDIX



Masonry deterioration


Condition: • Mortar deterioration

Mortar cracks noted throughout. Structural movement suspected. Have mortar repaired by licensed masonry contractor as needed throughout prior to closing.

Implication(s): Chance of water entering house | Weakened structure | Chance of structural movement

Location: Throughout

Task: Repair
Time: Immediate



3700 S. Central, Cicero, IL October 17, 2013

www.insightinspec.com

SUMMARY

ROOFING

EXTERIOR

STRUCTURE ELECTRICAL

PLUMBING

APPENDIX







Mortar deterioration

EXTERIOR GLASS \ General

Condition: • Glass block below grade. May contribute to water entry in basement. Cracked block. Replacement of glass block with solid brick is recommended. Have evaluated and repaired as needed by licensed masonry contractor.



Window below grade; chance of water entry

EXTERIOR GLASS \ Exterior trim

Condition: • Caulking loose, missing or deteriorated

Implication(s): Chance of water damage to contents, finishes and/or structure | Increased heating and cooling costs

Task: Service

Time: Regular maintenance

3700 S. Central, Cicero, IL

Report No. 1398, v.2 www.insightinspec.com

PLUMBING SUMMARY ROOFING EXTERIOR STRUCTURE ELECTRICAL APPENDIX



Deteriorating caulk at windows throughout

PORCHES, DECKS, STEPS, PATIOS AND BALCONIES \ Steps and landings

October 17, 2013

Condition: • Masonry or concrete cracking

Previous cosmetic repairs. Front steps are cracking. Loose concrete, loose handrail. Have steps replaced by licensed masonry contractor prior to closing.

Implication(s): Weakened structure

Location: Front Task: Replace Time: Immediate



Loose materials



Masonry or concrete cracking

3700 S. Central, Cicero, IL October 17, 2013 www.insightinspec.com

SUMMARY

ROOFING

EXTERIOR

STRUCTURE ELECTRICAL

AL HEAT

COOLI

PLUMBING

INTERIO


APPENDIX

OUTBUILDING / GARAGE \ Vehicle door operators

Condition: • Inoperative

Yard-side vehicle door failed to close due to tangled cable. Have repaired as needed by licensed garage door repairman prior to closing.

Implication(s): System inoperative



Tangled cable

3700 S. Central, Cicero, IL October 17, 2013 www.insightinspec.com

SUMMARY

ROOFING

TERIOR

STRUCTURE ELEC

CAL HEAT

COOLIN

PLUMBING

INTERIO

APPENDIX

Description

Configuration: • Basement

Foundation material: • Poured concrete • Not visible

Floor construction: • Joists

Exterior wall construction: • Masonry

Roof and ceiling framing: • Rafters/roof joists • Plank sheathing

Limitations

Inspection limited/prevented by: • Carpet/furnishings • Storage • New finishes/paint

Attic/roof space: • Inspected from access hatch

Percent of foundation not visible: • 100 %

Recommendations

General

• Possible insect activity noted at NE corner of building at basement. Unidentified "sawdust-like" material was observed in electrical panel. This material may be related to insect activity. Further evaluation by a licensed pest contractor specializing in wood-destroying organisms is recommended prior to closing.



Unidentified debris in electrical panel.

• Main stairway is pulling away from trim stringer at north. It appears that the top of the stairway has moved approximately 1-1/2" laterally away from the wall. Further review and repair as needed by licensed structural contractor is recommended prior to closing.

3700 S. Central, Cicero, IL October 17, 2013

SUMMARY

ROOFING

STRUCTURE



Lateral movement at stairway

FOUNDATIONS \ Performance opinion

Condition: • Suspect

Fully finished basement prevented direct observation of the foundation. Foundation performance is suspect due to exterior masonry cracks and elevated moisture levels detected in basement. See water intrusion notes in "Interior" section of this report.

Further evaluation of foundation by waterproofing specialist is recommended prior to closing. Further evaluation of foundation (when exposed) by licensed home inspector or structural engineer is recommended.

Implication(s): Chance of structural movement

Task: Further Evaluation

FLOORS \ Joists


Condition: • Notches or holes Implication(s): Weakened structure

Location: Throughout

Task: Repair Time: Immediate 3700 S. Central, Cicero, IL

SUMMARY ROOFING STRUCTURE COOLING PLUMBING **APPENDIX**

October 17, 2013







Notches or holes

Notches or holes

WALLS \ Solid masonry walls

Condition: • Prior repairs

Implication(s): Weakened structure

Location: Throughout

Condition: • Cracked

Cracked window sills indicate structural movement. Have repaired or replaced as needed by licensed masonry

contractor prior to closing.

Implication(s): Weakened structure Location: South 1st & 2nd floors

Task: Repair/Replace

www.insightinspec.com

www.insightinspec.com

SUMMARY ROOFING EXT

3700 S. Central, Cicero, IL

October 17, 2013

STRUCTURE

ELECTRIC

HEATING

COOLING

PLUMBING

INTERIOR

APPENDIX



Cracked sill

Condition: • Masonry deteriorating

Implication(s): Weakened structure | Chance of structural movement

Location: Various Task: Repair Time: Immediate

Condition: • Lintels rusting

Have lintels serviced as needed when tuck-pointing exterior of structure. It appears that a window was removed and bricked up at the north. The lintel was left in the wall, and is now deteriorating and pushing the bricks apart. Have repaired as needed by licensed masonry contractor.


Implication(s): Weakened structure | Chance of structural movement

Location: Throughout

Task: Service **Time**: Immediate

3700 S. Central, Cicero, IL

October 17, 2013 SUMMARY ROOFING STRUCTURE PLUMBING APPENDIX





Lintels rusting

Condition: • Mortar deteriorating

Implication(s): Weakened structure | Chance of structural movement

Location: Throughout

Task: Repair Time: Immediate

WALLS \ Lintels

Condition: • Space above lintel has been filled with caulk. This space should be left open. It is supposed to provide drainage for the wall cavity. Caulking the lintel can contribute to interior water problems, and will contribute to rust and premature failure of the lintel.

Lintel should be checked and serviced as needed by an experienced, licensed and insured masonry contractor prior to

www.insightinspec.com

STRUCTURE

Report No. 1398, v.2

Page 20 of 38

3700 S. Central, Cicero, IL October 17, 2013 www.insightinspec.com

HEATING COOLING PLUMBING SUMMARY STRUCTURE ELECTRICAL APPENDIX closing. **ROOF FRAMING \ Sheathing** Condition: • Water stains Implication(s): Material deterioration

Inspected with Acuity

www.insightinspec.com

3700 S. Central, Cicero, IL October 17, 2013

SUMMARY

ROOFING

EXTERIOR

CTURE E

ECTRICAL

HEATING

COOLIN

PLUMBING

INTERIO

APPENDIX

Description

Service entrance cable and location: • Overhead

Service size: • 100 Amps (240 Volts)

System grounding material and type: • Copper - water pipe

Distribution panel type and location: • Breakers - basement

Distribution wire material and type: • Copper - conduit

Type and number of outlets (receptacles): • Grounded - typical

Circuit interrupters: Ground Fault (GFCI) & Arc Fault (AFCI): • GFCI - kitchen and bathrooms • GFCI-Exterior

Smoke detectors: • Present

Carbon monoxide (CO) detectors: • None noted

Limitations

System ground: • Continuity not verified • Quality of ground not determined

Circuit labels: • The accuracy of the circuit index (labels) was not verified.

Recommendations

General

• Any electrical recommendations should be considered high priority items, since all electrical issues are safety concerns.

SERVICE BOX, GROUNDING AND PANEL \ Distribution panel

Condition: • Panel checked



Panel checked

3700 S. Central, Cicero, IL October 17, 2013

SUMMARY

ROOFING

FXTERIO

STRUCTURE

LECTRICAL

HEATING

COOLIN

PLUMBING


INTERIO

APPENDIX

SERVICE BOX, GROUNDING AND PANEL \ Distribution fuses/breakers

Condition: • <u>Double taps</u> **Implication(s)**: Fire hazard

Location: Panel Task: Correct Time: Immediate





Double taps

3700 S. Central, Cicero, IL

SUMMARY

ROOFING

EXTERIOR

STRUCTUR

October 17, 2013

ELECTRICAL

HEATING

COOLIN

PLUMBING

INTERIO

APPENDIX


DISTRIBUTION SYSTEM \ Outlets (receptacles)


Condition: • GFI protected by GFI upstream. Nuisance. Have corrected by licensed electrician prior to closing.

Location: Kitchen
Task: Correct
Time: Discretionary

Condition: • Reversed polarity Implication(s): Electric shock

Location: Addition Task: Correct Time: Immediate





3700 S. Central, Cicero, IL October 17, 2013

SUMMARY

ROOFING

STRUCTURE ELECTRICAL

APPENDIX

Condition: • Ground needed for 3-slot outlet

Implication(s): Electric shock

Location: Throughout

Task: Correct Time: Immediate

Condition: • Arc Fault Interrupter (AFI) needed

Current national standards require Arc Fault Interrupter (AFI) outlets for all bedroom outlet circuits. Have AFI breakers added as needed by licensed electrician to enhance the safety of the electrical system. For more information about AFI protection, see "Appendix" section of this report.

Location: Panel Task: Install Time: Immediate

DISTRIBUTION SYSTEM \ Cover plates

Condition: • Missing

Implication(s): Electric shock

Location: Kitchen Task: Install Time: Immediate



Missing cover plates

www.insightinspec.com 3700 S. Central, Cicero, IL October 17, 2013

SUMMARY ROOFING

STRUCTURE ELECTRICAL

HEATING

PLUMBING

APPENDIX

Description

Fuel/energy source: • Gas

System type: • Furnace

Furnace manufacturer: • Frigidaire

Heat distribution: • Ducts and registers

Approximate capacity: • 95,000 BTU/hr

Efficiency: • Mid-efficiency

Approximate age: • 13 years

Typical life expectancy: • Furnace (conventional or mid-efficiency) 18 to 25 years

Main fuel shut off at: • Meter

Combustion air source: • Interior of building

Limitations

Safety devices: • Not tested as part of a building inspection

Heat loss calculations: • Not done as part of a building inspection

Heat exchanger: • Only a small portion visible

Recommendations

RECOMMENDATIONS \ Overview

Condition: • Annual maintenance by licensed appliance technician is recommended to ensure system efficiency and maximum service life.

GAS FURNACE \ Ducts, registers and grilles

Condition: • Poor location

Opening in return plenum can lead to carbon monoxide entering the living space. Carbon monoxide is a colorless, odorless, deadly poisonous gas. This opening must be properly sealed to prevent carbon monoxide poisoning. Have furnace reviewed and corrected as needed by licensed HVAC tech prior to use.

Location: Furnace Task: Correct Time: Immediate

3700 S. Central, Cicero, IL October 17, 2013

SUMMARY

ROOFING

FXTERIO

STRUCTURE

ELECTRICA


HEATING


COOLING

PLUMBING

INTERIOR

APPENDIX





Paper indicates this is return (suction) duct



Openings in return duct are hazardous here

COOLING & HEAT PUMP

3700 S. Central, Cicero, IL October 17, 2013

Report No. 1398, v.2

www.insightinspec.com

SUMMARY ROOFING EXTERIOR STRUCTURE ELECTRICAL HEATING COOLING PLUMBING INTERIOR APPENDIX

Description

Manufacturer: • Frigidaire


Compressor approximate age: • 13 years

Typical life expectancy: • 10 to 15 years

Failure probability: • High • Medium

Limitations

Inspection limited/prevented by: • Damage to the compressor can result if the outdoor temperature has not been above 65 degrees for 12 hours prior to testing. Therefore, the air conditioning system was not tested at this inspection.



Inspection limited/prevented by: • Low outdoor temperature

Heat gain/loss calculations: • Heat gain and loss calculations are not performed as part of a home inspection. These calculations are typically performed by designers to determine the required size for heating and cooling systems prior to installation.

3700 S. Central, Cicero, IL October 17, 2013

SUMMARY ROOFING

STRUCTURE ELECTRICAL

PLUMBING

APPENDIX

Description

Water supply source: • Public

Service piping into building: • Not visible

Supply piping in building: • Copper • Galvanized steel

Main water shut off valve at the: • Front of the basement

Water flow and pressure: • Functional

Water heater fuel/energy source: • Gas

Water heater type: • Conventional Waste disposal system: • Public

Waste piping in building: • Cast Iron • Galvanized steel • Not visible

Gas piping: • Steel

Limitations

Items excluded from a building inspection: • Floor Drains • Sealed catch basins • Buried plumbing

Items excluded from a building inspection: • Water quality • Isolating/relief valves & main shut-off valve • Concealed

plumbing • Tub/sink overflows • Water heater relief valves are not tested

Recommendations


SUPPLY PLUMBING \ Supply piping in building

Condition: • Galvanized steel

Supply piping is a mix of newer copper and older galvanized steel. The galvanized has a service life of 50 years. After that time, problems can develop, including leakage and reduced water pressure. Replacement of the remaining steel supply pipe is recommended as a preventative measure. Timing is discretionary, but should probably be done within the next 5-10 years.

www.insightinspec.com

SUMMARY ROOFING EXTERIOR STRUCTURE ELECTRICAL HEATING COOLING PLUMBING INTERIOR APPENDIX





Galvanized steel and copper supply pipe

WATER HEATER \ Tank

Condition: • Safety pan and drain missing

Implication(s): Chance of water damage to contents, finishes and/or structure

3700 S. Central, Cicero, IL October 17, 2013

SUMMARY

ROOFING

EXTERIOR

STRUCTURE ELECTRICAL

HEA1

COOLI

PLUMBING

INTERIO

APPENDIX

WATER HEATER \ Temperature/pressure relief valve

Condition: • Discharge tube threaded

Have water heater TPR discharge tube replaced in accordance with manufacturer's instructions by licensed and insured plumbing contractor prior to closing. A straight copper tube of the proper diameter and length is preferred.

Implication(s): Steam explosion



Discharge tube threaded, not straight

WATER HEATER - GAS BURNER AND VENTING \ Venting system

Condition: • Improper material

Flexible ductwork used as vent connector. Improper slope; may cause backdrafting of combustion gasses into house. Have reviewed by licensed plumbing or heating contractor and repair as needed.

Implication(s): Equipment not operating properly | Hazardous combustion products entering home



Improper material/poor support

PLUMBING

3700 S. Central, Cicero, IL October 17, 2013

Report No. 1398, v.2

www.insightinspec.com

SUMMARY ROOFING EXTERIOR STRUCTURE ELECTRICAL HEATING COOLING PLUMBING INTERIOR APPENDIX

FIXTURES AND FAUCETS \ Basin, sink and laundry tub

Condition: • Drain stop ineffective

Implication(s): Nuisance | Reduced operability

Location: Second Floor Bathroom

Task: Repair

Time: Discretionary

FIXTURES AND FAUCETS \ Toilet

Condition: • Damaged flush handle

Task: Replace handle **Time**: Discretionary

3700 S. Central, Cicero, IL October 17, 2013

SUMMARY

ROOFING

STRUCTURE ELECTRICAL

COOLING

PLUMBING

INTERIOR

APPENDIX

Description

Major floor finishes: • Hardwood

Major wall finishes: • Plaster/drywall

Major ceiling finishes: • Plaster/drywall

Windows: • Single/double hung • Vinyl

Glazing: • Double

Evidence of basement leakage: • Present • Stains • Dampness • Mold • Mildew • Rot • Loose floor tiles

Oven fuel: • Gas Range fuel: • Gas

Laundry facilities: • Washer • Laundry tub • Hot/cold water supply • Dryer • Vented to outside

Limitations

General: • A HOME INSPECTION IS NOT A PEST INSPECTION. Insects, rodents, or wildlife of any kind are not included in this inspection. You are encouraged to retain an appropriately licensed pest inspector if you would like a pest inspection.

Inspection limited/prevented by: • Storage/furnishings • New finishes/paint • Storage in closets/cupboards

Not tested/not in service: • Refrigerator

Not tested/not in service: • Range • Oven • Microwave

Not included as part of a building inspection: • Telephone lines, cable television reception, antennas, digital cable, satellite dishes and all other electronic, digital, or fiber optic communication systems are not included in a home inspection. • Audio, Video, Computer, or Entertainment Systems

Not included as part of a building inspection: • Carbon monoxide detectors • Cosmetic issues • Appliances • Perim eter drainage tile around foundation, if any

Cosmetics: • No comment offered on cosmetic finishes

Appliances: • Appliances are not inspected as part of a building inspection • Appliances are not moved during an inspection

Percent of foundation not visible: • 100 %

Basement leakage: • Cannot predict how often or how badly basement will leak

Recommendations

FLOORS \ Ceramic tile, stone, marble, etc

Condition: • Grout missing

Implication(s): Cosmetic defects | Trip or fall hazard

Location: North


3700 S. Central, Cicero, IL October 17, 2013 www.insightinspec.com

SUMMARY ROOFING EXTERIOR STRUCTURE ELECTRICAL HEATING COOLING PLUMBING INTERIOR APPENDIX

Condition: • Tiles missing

Implication(s): Cosmetic defects | Trip or fall hazard

Location: North
Task: Correct



WALLS \ General

Condition: • Typical flaws

Implication(s): Cosmetic defects

Location: Throughout

WALLS \ Plaster or drywall

Condition: • Water damage

Very high moisture levels noted at basement interior at south and east. Advanced rot and deterioration observed at weight room (south side near front of building). Mold or mildew staining observed at south and east.

Extremely high moisture levels were observed; it is almost a certainty that rot and mold will be found once the drywall has been removed.

Mold testing was not performed at this inspection.

Drywall should be removed as needed throughout basement, to facilitate further investigation and repair. Foundation cracks are probably present, but could not be directly observed due to the presence of drywall. Have basement leaks repaired by licensed basement waterproofing contractor prior to closing.

Implication(s): Cosmetic defects Location: Throughout Basement Task: Further evaluation/Repair

Time: Immediate

3700 S. Central, Cicero, IL October 17, 2013

SUMMARY


ROOFING

PLUMBING

INTERIOR

APPENDIX







Water damage, elevated moisture, basement eas



Water damage, high moisture levels, basement

Condition: • Cracked

Large wall crack noted at south, second floor. Indication of structural movement. Have repaired as needed prior to

closing.

Task: Repair Time: Ongoing

SUMMARY

ROOFING

3700 S. Central, Cicero, IL

FXTERIO

STRUCTUR

October 17, 2013

ELECTRICA

HEATING

COOLIN

PLUMBING

INTERIOR

APPENDIX



Cracked wall

CEILINGS \ General

Condition: • Water damage

Water damage, blistering plaster noted at second floor, east. Area was scanned with moisture meter; elevated moisture levels were detected. An active leak is suspected. May be related to either failed chimney flashing or the overall poor condition of the roof. Have water source positively identified and repaired prior to repair of interior finished surfaces.

Elevated moisture levels may support mold growth. Mold testing was not performed at this inspection.

Implication(s): Cosmetic defects | Chance of movement



Elevated moisture readings (18%)



Water damage

INTERIOR

Report No. 1398, v.2

3700 S. Central, Cicero, IL October 17, 2013

www.insightinspec.com

SUMMARY ROOFING EXTERIOR STRUCTURE ELECTRICAL HEATING COOLING PLUMBING INTERIOR APPENDIX

Condition: • Typical flaws **Implication(s)**: Cosmetic defects

Location: Throughout

END OF REPORT

Report No. 1398, v.2 www.insightinspec.com

SUMMARY ROOFING EXTERIOR STRUCTURE ELECTRICAL HEATING COOLING PLUMBING INTERIOR APPENDIX



CPSC Fact Sheet

Preventing Home Fires: Arc Fault Circuit Interrupters (AFCIs)

Problems in home wiring, like arcing and sparking, can cause fires in the home.

Arc fault circuit interrupters or AFCIs, can provide enhanced protection from fires resulting from these unsafe home wiring conditions.

Typical household fuses and circuit breakers do not respond to early arcing and sparking conditions in home wiring. By the time a fuse or circuit breaker opens a circuit to defuse these conditions, a fire may already have begun.

AFCIs vs. GFCIs

AFCIs should not be confused with ground fault circuit interrupters or GFCIs. The popular GFCI devices are designed to provide protection from the serious consequences of electric shock.

While both AFCIs and GFCIs are important safety devices, they have different functions. AFCIs are intended to address fire hazards; GFCIs address shock hazards. Combination devices include both AFCI and GFCI protection in one unit.

Should You Install AFCIs?

You may want to consider adding AFCI protection for both new and existing homes. Older homes with ordinary circuit breakers especially may benefit from the added protection against the arcing faults that can occur in aging wiring systems.

For more information about AFCIs, contact an electrical supply store, an electrician, or the manufacturer of the circuit breakers already installed in your home. Sometimes these components can be replaced with AFCIs in the existing electrical panel box.

Be sure to have a qualified electrician install AFCIs; do not attempt this work yourself. The installation involves working within electrical panel boxes that are usually electrically live, even with the main circuit breakers turned off.

Publication 5133 R042012

U.S. Consumer Product Safety Commission, Bethesda, MD 20814 ● (800) 638-2772 ● www.cpsc.gov ● www.saferproducts.gov

SUMMARY

ROOFING

FYTER

STRUCTUR

ELECTRIC

HEATING

COOLING

PLUMBING

INTERIO

APPENDIX



CPSG Safety Alert


Overheated Clothes Dryers Can Cause Fires

Fires can occur when lint builds up in the dryer or in the exhaust duct. Lint can block the flow of air, cause excessive heat build-up, and result in a fire in some dryers.

To help prevent fires:

- Clean the lint screen/filter before or after drying each load of clothes. If clothing is still damp at the end of a typical drying cycle or drying requires longer times than normal, this may be a sign that the lint screen or the exhaust duct is blocked.
- Clean the dryer vent and exhaust duct periodically. Check the outside dryer vent while the dryer is operating to make sure exhaust air is escaping. If it is not, the vent or the exhaust duct may be blocked. To remove a blockage in the exhaust path, it may be necessary to disconnect the exhaust duct from the dryer. Remember to reconnect the ducting to the dryer and outside vent before using the dryer again.
- Clean behind the dryer, where lint can build up. Have a qualified service person clean the interior of the dryer chassis periodically to minimize the amount of lint accumulation. Keep the area around the dryer clean and free of clutter.

- Replace plastic or foil, accordion-type ducting material with rigid or corrugated semi-rigid metal duct. Most manufacturers specify the use of a rigid or corrugated semi-rigid metal duct, which provides maximum airflow. The flexible plastic or foil type duct can more easily trap lint and is more susceptible to kinks or crushing, which can greatly reduce the airflow.
- Take special care when drying clothes that have been soiled with volatile chemicals such as gasoline, cooking oils, cleaning agents, or finishing oils and stains. If possible, wash the clothing more than once to minimize the amount of volatile chemicals on the clothes and, preferably, hang the clothes to dry. If using a dryer, use the lowest heat setting and a drying cycle that has a cool-down period at the end of the cycle. To prevent clothes from igniting after drying, do not leave the dried clothes in the dryer or piled in a laundry basket.



Publication 5022 062003 022012

U.S. CONSUMER PRODUCT SAFETY COMMISSION • (800) 638-2772 • www.cpsc.gov • www.SaferProducts.gov